

Institut "Jožef Stefan", Ljubljana, Slovenija

Plans and Readiness for the October DRD3 2025 Test Beam Campaign

Iskra Velkovska

05/09/2025


- 1) **Test beam DRD3 in October (1-15) for 2 weeks (priority in the second week -> V1)**
- 2) **Samples to be tested: TI-LGADs Wafer 2 trench border versions: V1 + V2, TW 1/2/3/4/5/6/7 TR1**
- 3) **Will 3D FBK structures be tested?**
- 4) **Manpower at the test beam ?**
- 5) **Infrastructure for the upcoming testbeam**
- 6) **Samples were irradiated @TRIGA reactor at JSI and were annealed for 80 min @ 60 °C**
- 7) **Google sheet for the upcoming test beam: [October testbeam 2025](#)**

TI-LGAD test structures


45 μm thick sensors

375 μm $\times$ 250 μm pixel pitch


Border version	Number of Trenches
V2	1TR
V1	1TR
V2	1TR
V2	2TR



V2 - 1TR- TW 4/6/7



V1/2 - 1TR- TW 5



V2 - 1TR- TW 1/2/3

Batches and schematics proposal



Trench Depth	Trench parameter	Fluence (n _e q/cm ²)	Devices	Number of daughterboard	Chubut CH1,2	Chubut CH3,4	Batch Number (proposed)
V1	TW5	2.50E+15	V1TW5 / V2TW5	1	V1TW5	V2TW5	1
V1	TW5	2.50E+15	V1TW5 / V2TW5	2	V1TW5	V2TW5	2
V1	TW5	2.50E+15	V1TW5 / V2TW5	3	V1TW5	V2TW5	3
V1	TW5	2.50E+15	V1TW5 / V2TW5	4	V1TW5	V2TW5	
					V1TW5	V2TW5	1
V1	TW5	1.50E+15	V1TW5 / V2TW5	5	V1TW5	V2TW5	2
V1	TW5	1.50E+15	V1TW5 / V2TW5	6	V1TW5	V2TW5	
V1	TW5	1.50E+15	V1TW5 / V2TW5	7	V1TW5	V2TW5	3
V2	TW 4/6/7	1.50E+15	Standard	8			
V2	TW 4/6/7	1.50E+15	Standard	9	V2TW4	V2TW6	3
V2	TW 4/6/7	2.50E+15	Standard	10	V2TW4	V2TW6	2
V2	TW 4/6/7	2.50E+15	Standard	11	V2TW4	V2TW6	3
V2	TW 1/2/3	1.50E+15	Standard	12	V2TW1	V2TW2	2
V2	TW 1/2/3	2.50E+15	Standard	13	V2TW1	V2TW2	1
V2	TW 1/2/3	2.50E+15	Standard	14	V2TW2	V2TW3	1
From previous test beam							
V2	TW 1/2/3	8.00E+14	Standard	15	V2TW1	V2TW2	Backup
V2	TW 1/2/3	1.50E+15	Standard	16	V2TW1	V2TW2	Backup





Current–Voltage Characteristics of TI-LGADs

Extraction of V_{gl} and V_{bd}



I-V Curve Validation of V1 TW5 TI-LGAD after 1.5×10^{15} n_{eq}/cm^2 irradiation





I–V Curve Validation of V2 TW5 TI-LGAD after 1.5×10^{15} n_{eq}/cm^2 irradiation





I-V Curve Validation of V1 TW5 TI-LGAD after 2.5×10^{15} n_{eq}/cm^2 irradiation





I-V Curve Validation of V2 TW5 TI-LGAD after 2.5×10^{15} n_{eq}/cm^2 irradiation





I-V Curve Validation of V2 TW1 TI-LGAD after 1.5×10^{15} n_{eq}/cm^2 irradiation





I-V Curve Validation of V2 TW2 TI-LGAD after 1.5×10^{15} n_{eq}/cm^2 irradiation





I-V Curve Validation of V2 TW3 TI-LGAD after 1.5×10^{15} n_{eq}/cm^2 irradiation





I-V Curve Validation of V2 TW1 TI-LGAD after 2.5×10^{15} n_{eq}/cm^2 irradiation




I-V Curve Validation of V2 TW2 TI-LGAD after 2.5×10^{15} n_{eq}/cm^2 irradiation



I–V Curve Validation of V2 TW3 TI-LGAD after 2.5×10^{15} n_{eq}/cm^2 irradiation



Acceptor removal of V2 TW1/2/3 TI-LGAD





TW1: $c \approx 1.44 \times 10^{-16} \text{ cm}^2$



TW2: $c \approx 1.90 \times 10^{-16} \text{ cm}^2$

TW3: $c \approx 1.68 \times 10^{-16} \text{ cm}^2$



I-V Curve Validation of V2 TW4 TI-LGAD after 1.5×10^{15} n_{eq}/cm^2 irradiation





I-V Curve Validation of V2 TW6 TI-LGAD after 1.5×10^{15} n_{eq}/cm^2 irradiation




I-V Curve Validation of V2 TW4 TI-LGAD after 2.5×10^{15} n_{eq}/cm^2 irradiation



I-V Curve Validation of V2 TW6 TI-LGAD after 2.5×10^{15} n_{eq}/cm^2 irradiation



Acceptor removal of V2 TW 4/6 TI-LGAD



TW4: $c \approx 1.30 \times 10^{-16} \text{ cm}^2$

TW6: $c \approx 1.76 \times 10^{-16} \text{ cm}^2$